BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 22nd March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 15th April 1933, for "Improving the Water Supply Scheme to Robertsonpet." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Sanitary Engineer's Office, between the hours of 11 A.M. to 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates quoted should be for the items as described in this Notice. The tenderers are forbidden to change the nomenclature of the items and quote rates.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash as earnest money, and be superscribed "Tender for Improving the Water Supply Scheme to Robertsonpet" in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Executive Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Abstract Estimate of quantities for Improving the Water Supply Scheme to Robertsonpet. (All the materials being supplied by the Department).

Sl. No.	Items of work	Unit	Quantity
	Removing, cleaning and Relaying the existing 3" and 2½" cast Iron Main from tank to Carr Road along the 1st Cross Road.		
1	Earthwork excavation, refilling and tamping and bringing the road surface to original condition.	C.yd.	694
2	Removing 3" C. I. pipes 2750 R.ft. of 9' long and 128 lbs each.	Cwt.	349
3	Removing 2½" C. I. pipes 250 feet of 9' long and 112 lbs. each.	,,	28
4	Cleaning 3" and 2½" C. I. pipes rubbing the socket and spigot ends inside.	R.ft.	3,000
5	Making lead joints to 3" C. I. pipes including laying and jointing complete with ends wherever necessary 10 per cent of the total number of removed pipes.	Each.	30
6	Making cement joints to 3" C. I. pipe including laying and jointing complete with cuts.	,,	275
7	Making lead joints to 2½ C. I. pipe including laying and jointing complete with cuts.	,,	3
8	Making cement joints to 2½" C. I. pipes including laying and jointing complete.	,,	25
	Cleaning 2½" C. I. pipes and 1½" G. I. pipes from Carr Road to 7th Cross Road up to the Police Lines, Robertsonpet.		
1	Earthwork excavation, refilling and tamping and bringing	C.yd.	354

Sl. No.	Items of work	Unit	Quantity
2	Removing 2½" C. I. pipes 1420' of 9' lengths ...	Cwt.	158
3	Removing 1½" G. I. pipes	R.ft.	300
4	Cleaning do	,,	300
5	Making lead joints 2½" C. I. pipe including laying and jointing complete with cuts wherever necessary.	No.	15
6	Making cement joints to 2½" pipes including laying and jointing with cuts wherever necessary.	,,	143
7	Laying and jointing 1½" G. I. pipes including cutting and threading without earthwork.	R.ft.	300
	Laying 3" C. I. pipe in Maharaja Road, Robertsonpet.		
1	Earthwork excavation, refilling, tamping and bringing the road surface to original condition.	Cyd.	300
2	C. I. cuts 3"	No.	2
3	Removing 3" C. I. pipes at connection	Cwt.	2
4	Making lead joints to 3" C. I. pipe including laying and jointing complete with cuts wherever necessary.	No.	14
5	Making cement joints to 3" G. I. pipes including laying and jointing complete with cuts wherever necessary.	,,	130
6	Fixing C. I. valves 3" with rubber insertion ...	,,	2
7	Removing 1½" G. I. pipe	R.ft.	400
	Laying 5" C. I. Pipes from the Tank to Carr Road in Robertsonpet.		
1	Earthwork excavation, refilling, tamping and bringing the road surface to original condition. ...	Cyd.	628
2	Making 5" lead joints.	No.	25
3	5" C. I. cuts	Nos.	2
4	5" Cement joints	No.	210
5	Fixing 5" C. I. valve	,,	1
6	Constructing valve cistern with shutters	,,	1

B. R. GARUDACHAR,
Executive Sanitary Engineer.

BANGALORE DIVISION.

Notification dated 25th March 1933.

Notice is hereby given that the sealed quotations will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 24th April 1933 for "Constructing a New Tank near Kannaikan Agrahahar village of Anekal Taluk". An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division Bangalore, between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The quotations should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash as earnest money and be superscribed "Tender for Constructing a New Tank near Kannaikan Agrahara Village of Anekal Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.